



QUOTE

QUO-050

FROM

Lakeside Painting
Wanaka, New Zealand
022 106 0336
info@lakesidepainting.co.nz
lakesidepainting.co.nz

PREPARED FOR

Vivek Patel (Dimension Shopfitters)
Vivek@dimensionshopfitters.co.nz
+64 21 522 983
20 Helwick Street, Wanaka 9305

DETAILS

Date: 14/07/2026
Ref: R&G Wanaka
Project: Rodd & Gunn Fit-out
Valid: 30 days

Description	Amount
Site setup, floor and fixture protection, masking	\$800.00
Standard preparation: filling, sanding, spot-priming and making good of affected surfaces, ready for the specified finish	\$1,700.00
Repaint existing walls within the nominated retail painting areas to match existing, two coats	\$2,450.00
W-01 Vivid White to T&G feature cladding, new ceiling trim and skirting	\$2,100.00
W-02 Bottle Green to both fitting rooms	\$1,150.00
W-03 Dark Charcoal to shopfront lower wall panels	\$450.00
Shopfront fascia and wall, made good and repainted to match existing	\$750.00
Final site clean and rubbish removal	\$150.00
Subtotal (excl. GST)	\$9,550.00
GST (15%)	\$1,432.50
Total (incl. GST)	\$10,982.50

WHAT'S INCLUDED

- ✓ All labour: preparation, priming and finish coats
- ✓ Premium Dulux paint throughout, two coats (three to dark colours where needed)
- ✓ New wall finishes per Finishes Schedule: W-01 Vivid White, W-02 Bottle Green, W-03 Dark Charcoal
- ✓ Paint finish to new T&G cladding and skirting (installed by others)
- ✓ Floor and fixture protection, masking and full clean-up
- ✓ Colour sample boards for client sign-off before we start

NOT INCLUDED

- Signage, lighting, electrical, data, heat pump, MEP and speakers
- Supply and install of fixtures, curtains, tracks and TV
- Existing fitting-room mirrors and their electrical, disconnected, removed and reinstated by others (before and after painting)
- Supply and install of T&G cladding and skirting joinery (we paint only)
- Flooring supply and the professional floor clean
- Repainting of the rear stockroom, storage and staff areas (excluded unless specifically shown within the confirmed painting scope)
- Full ceiling repaint (finishes schedule and reflected ceiling plan conflict on ceiling scope; any ceiling repair or repaint to be priced once the scope is confirmed)
- Major repairs, re-skimming, consent, fire-rated coatings and PS3

ESTIMATED TIMELINE

Start: TBC with Dimension

Duration: Approx. 6 working days (2-person crew)

Note: Construction programme not yet issued, so happy to fit the painting around your site dates.

TERMS & CONDITIONS

1. 30% deposit to secure the booking; balance on completion or by progress claim as agreed.
2. Making good covers minor filling and repair only. Significant repairs or re-skimming are quoted separately, or charged at \$80 per painter per hour plus materials, as a variation.
3. Assumes the new cladding and skirting are installed ready for paint, and the existing fitting-room mirrors removed and reinstated, by others.
4. All stock, loose furniture, artwork, shelving and retail fixtures to be removed or relocated by others before painting; pricing assumes clear, accessible work areas.
5. Colours priced per Finishes Schedule PPD-001; final colours confirmed by client sample sign-off.
6. Price valid 30 days from the date of this quote.

NOTES

Fixed lump sum for the painting scope only, priced off Proposed Design R00 (PPD-000 to PPD-513). Includes colour sample boards for your sign-off before we start.

Ready to go ahead?

Simply reply to this quote or give us a call on 022 106 0336 to confirm. We'll get your project booked in.

Thank you for considering Lakeside Painting