



QUOTE

QUO-058

FROM

Lakeside Painting
Wanaka, New Zealand
022 106 0336
info@lakesidepainting.co.nz
lakesidepainting.co.nz

PREPARED FOR

Cameron Leask (Latch Build)
cam@latchbuild.co.nz
027 333 3678
27 Burdon Loop, Lot 105 DP
605685, RD 2 Wanaka (Lake
Hawea)

DETAILS

Date: 07/08/2026
Ref: RAVE QR-241866-14
Project: New Build Painting Packa...
Valid: 60 days

Description	Amount
Site setup, floor and joinery protection, masking; sealer/undercoat to all new interior plasterboard, walls and ceilings throughout	\$4,200.00
Ceilings: two topcoats Resene ceiling flat white, Level 4 finish to all flat ceilings	\$2,000.00
Walls: two topcoats Resene low sheen acrylic; Lustercryl kitchen and bathroom enamel to bathroom, ensuite and laundry (wet areas per spec)	\$4,700.00
Trim: architraves (90mm), skirtings (60mm), sills and window reveals in Lusterglo semi-gloss enamel	\$2,600.00
Interior doors: 12 openings (hinged and robe sliders), both faces plus jambs, enamel finish	\$2,250.00
Garage: walls and ceiling, sealer plus two topcoats (Level 3 finish)	\$1,350.00
Exterior soffits: 4.5mm Hardies, three-coat exterior acrylic system	\$1,050.00
Exterior timber: two coats penetrating stain (natural) to vertical weatherboard accent cladding and timber fascia (stain product TBC on plans)	\$1,450.00
Final touch-ups after following trades and full site clean on completion	\$1,050.00
Subtotal (excl. GST)	\$20,650.00
GST (15%)	\$3,097.50
Total (incl. GST)	\$23,747.50

WHAT'S INCLUDED

- ✓ All labour and materials: preparation, sealing, undercoats and finish coats
- ✓ Resene systems per the project specification (Lustercryl wet areas, Lusterglo trim, low sheen walls, flat white ceilings)
- ✓ Brush and roller application as the spec requires, no site spraying without express permission
- ✓ Level 4 finish to all flat-ceiling rooms, Level 3 to garage
- ✓ Masking and protection of floors, glazing, joinery and prefinished surfaces
- ✓ Work staged around your build programme, with a return visit after fit-off
- ✓ Full site clean-up on completion

NOT INCLUDED

- Prefinished surfaces: Colorsteel roof and wall cladding, aluminium joinery, gutters, downpipes, garage door
- GIB stopping and plastering (by others)
- Wallpaper, specialist or fire-rated coatings
- Repairs to damage by other trades after handover of painted areas (variation at \$80 per painter per hour plus materials)
- Deep or bright colours needing a third coat (priced once colours are confirmed)
- Scaffolding beyond ladders and mobile tower (single-level build, none expected)

ESTIMATED TIMELINE

Start: Painting phase approx. Dec 2026 / Jan 2027 (ground broken mid-Sept, 6-month programme) **Duration:** Approx. 4 weeks on site (2-person crew), staged

Note: Interior main phase after stopping, exterior stain and soffits in fine weather, short return visit for touch-ups after fit-off. Happy to fit around your programme.

TERMS & CONDITIONS

1. Priced from the RAD developed concept drawings (Rev 1, 06/08/2026, sheets 1-25) and project specification, pre-consent. Price to be confirmed against the consented set; detail changes priced as variations.
2. Progress claims monthly or per stage as agreed with Latch Build; final balance on completion.
3. Price valid for 60 days from quote date, allowing for your consent timeline.
4. Variations at \$80 per painter per hour plus materials, agreed before work proceeds.
5. Assumes clear access, power on site, and surfaces handed over ready for paint (stopping by others).
6. Colour allowance is for standard Resene tints; final colours confirmed by client sign-off before painting starts.

NOTES

Priced brush and roller as the specification requires. If spraying is approved for ceilings and doors we can sharpen the price, happy to discuss. The weatherboard stain product is marked TBC on the plans; we've allowed two coats of penetrating stain and will confirm the system once the product is chosen.

Ready to go ahead?

Simply reply to this quote or give us a call on 022 106 0336 to confirm. We'll get your project booked in.