



QUOTE

QUO-061

FROM

Lakeside Painting
Wanaka, New Zealand
022 106 0336
info@lakesidepainting.co.nz
lakesidepainting.co.nz

PREPARED FOR

John Hassan
john.hassan@xtra.co.nz
027 241 2998
8 Primary Lane, Wanaka

DETAILS

Date: 22/08/2026
Ref: 8 Primary Lane
Project: Exterior Repaint
Valid: 30 days

Description

Amount

Preparation — full wash down, scrape and sand loose or flaking sections, caulk board-and-batten joins, spot seal and prime bare or chalky areas, masking and protection

\$3,400.00

Painting — spot coats to repaired areas plus one full coat to all painted marine ply / board-and-batten cladding (Resene Periglacial Blue), including Quarter Gravel base section

\$5,100.00

Materials — paint, sealer, caulk and sundries

\$1,200.00

Builder repairs — replace 2 timber trim pieces (1 vertical batten, 1 corner trim)

\$430.00

Subtotal (excl. GST)

\$10,130.00

GST (15%)

\$1,519.50

Total (incl. GST)

\$11,649.50

WHAT'S INCLUDED

- ✓ All preparation and painting labour
- ✓ Resene topcoats matched to existing colours (Periglacial Blue / Quarter Gravel)
- ✓ Caulking of board-and-batten joins
- ✓ Builder replacement of the two damaged trim pieces
- ✓ Full clean-up on completion

NOT INCLUDED

- Cedar restrain — available as an optional extra, see notes below
- Cedar soffits, fascia and garage door (can be priced on request)
- Powder-coated aluminium joinery (no coating required)

ESTIMATED TIMELINE

Start: From 10 December 2026

Duration: 4.5–5 working days

Note: We're adding crew at the moment, so an earlier start may open up — we'll let you know right away if it does. Exterior only, so work can be completed while you're away (water and power access required). Weather dependent.

TERMS & CONDITIONS

1. 30% deposit required to secure booking
2. Balance due on completion
3. Price valid for 30 days from quote date
4. Exterior work is weather dependent — we'll keep you updated on scheduling
5. Any additional work will be quoted separately

NOTES

Optional extras (excl. GST): second full topcoat to all board-and-batten cladding — \$2,400. Cedar restrain — wash and penetrating oil recoat to the cedar shiplap feature sections — \$2,500. Since we'll have everything set up on site, adding the cedar at the same time avoids a separate call-out later. Just let us know on acceptance if you'd like either included.

Ready to go ahead?

Simply reply to this quote or give us a call on 022 106 0336 to confirm. We'll get your project booked in.